

# RECONNECTING WATERWAYS

A WORKSHOP ON REMOVING DAMS & RIGHT-SIZING CULVERTS



(SLR, 2023)



# Dam Removal & Culvert Design Demystified

December 25, 2024  
Burlington, VT

SLRCONSULTING.COM





# Design Steps – Clean Water Initiative Program (CWIP)


<b>% Complete</b>	<b>Design Step</b>	<b>Description</b>
<b>60%</b>	PRELIMINARY	Project partners, regulators, landowners, funders, public representatives, and consultants work together to identify and assess the <b><u>scientific and engineering challenges and conceptual approaches</u></b> . Data Collection, Conceptual (10%) Plans, Alternatives Analysis, Site Surveys and Mapping, Meetings, 30% Design Calculations and analyses on designs, Preliminary (30%) design report
<b>100%</b>	FINAL	BUILD PROJECT. 60/90/100% Design, Final (100%) Design Report.

(VTDEC, 2022)



# Design Steps – VT Project Guide by TNC

FIGURE 3. Phases of a typical dam removal project





# Design Steps – WUV Grant Guidance

<b><i>Project Type</i></b>	<b><i>Definition</i></b>	<b><i>Performance measure</i></b>
Dam Removal – Preliminary Engineering Design	Preliminary design of a high priority dam removal project to restore hydrologic connectivity of surface waters. May involve alternatives analysis. Work must result in at least 30% design of project.	Number of preliminary (30%) designs completed
Dam Removal – Final Engineering Design	Final design of high priority dam removal project to restore hydrologic connectivity of surface waters. Work includes preparing permit application(s) and documentation of operation and maintenance plan(s).	Number of final (90%/100%) designs completed
Dam Removal – Implementation	Implementation of high priority dam removal project to restore hydrologic connectivity of surface waters. Permit(s), access license(s)/easement(s), and operation and maintenance plan(s) are in place prior to construction.	Acres of floodplain restored  Linear feet of stream restored  Stream miles reconnected for stream equilibrium/aquatic organism passage

(WUV, 2023)



# Design Steps - Demystified

<b>% Complete</b>	<b>Design Step</b>	<b>Description</b>
<b>10%</b> (0-20)	SKETCH	<ul style="list-style-type: none"><li>• INITIAL IDEAS. Project feasibility. Limited knowledge.</li></ul>
<b>30%</b> (20-40)	CONCEPT	<ul style="list-style-type: none"><li>• CONSTRAINTS, FOOTPRINT, INITIAL COST. Key constraints. Project footprint. Primary dimensions. Initial river profile. Ballpark cost. Seek landowner support.</li></ul>
<b>60%</b> (40-70)	PRELIMINARY	<ul style="list-style-type: none"><li>• REFINE DESIGN VISION AND COST. Lock in design path forward. Information for stakeholder understanding. Initial regulator review. Detail footprint, profile, section, and sediment management. Guide construction funding. Seek community support.</li></ul>
<b>90%</b> (70-95)	FINAL	<ul style="list-style-type: none"><li>• FINAL LANDOWNER AGREEMENT AND PERMITS. Access, construction details, sequence, final quantities, and refine cost.</li></ul>
<b>100%</b> (95-100)	CONSTRUCTION	<ul style="list-style-type: none"><li>• BUILD PROJECT. Edits from regulatory process.</li></ul>



# Design Step Selection

<b>% Complete</b>	<b>Project</b>	<b>Description</b>
90% Draft 100% Final	SIMPLE	<ul style="list-style-type: none"><li>• No constraints.</li><li>• No risk to property and infrastructure.</li><li>• Small river channel profile change anticipated.</li><li>• Long-term, breached, obsolete dam.</li><li>• Coarse sediment.</li><li>• Minimal permitting.</li></ul>
30% Concept 90% Draft 100% Final	MEDIUM	<ul style="list-style-type: none"><li>• Some constraints.</li><li>• Some potential short term instability influencing property or infrastructure requiring stabilization.</li><li>• Profile change expected.</li><li>• Larger dam with accumulated sediment.</li><li>• Moderate permitting.</li></ul>
30% Concept 60% Preliminary 90% Draft 100% Final	COMPLEX	<ul style="list-style-type: none"><li>• Major constraints.</li><li>• Channing instability potential for long term.</li><li>• Long-distance profile change possible.</li><li>• Large amount of accumulated sediment.</li><li>• Sensitive receiving waters.</li><li>• Complex permitting.</li></ul>





# Sediment



- Volume (cubic yards)
- Toxics
- Nutrients
- Disposal
- Amount likely to move

# Sediment




Figure 4: Breached Clark Saw Mill Dam (looking upstream on July 28, 2023)






# Hydraulics



- Profile
- Channel change
- Validation for flooding and normal flows
- Aquatic organism passage
- Flood reductions
- New hydraulic controls



# Longitudinal Profile




**LONG CHANNEL PROFILE**  
SCALE: H: 1"=100', V: 1"=5'



# Longitudinal Profile

## LONG CHANNEL PROFILE

SCALE: H: 1"=40', V: 1"=5'



## PROJECT CHANNEL PROFILE

SCALE: H: 2"=40', V: 1"=5'



# Alternatives Analysis – Dam Removal

1. None
  - A. Safety risk
  - B. Environmental risk
2. Partial removal
  - A. Feasibility
3. Full removal
  - A. Benefits




# Alternatives Analysis – Sediment Removal

1. None
  - A. Risk
2. Lower impoundment (limited)
  - A. Approximately half of the sediment
  - B. Would leave an over-steepened channel at bridge abutment to hold remaining sediment in place
  - C. Risk of sedimentation and nutrient loading remains high
3. **Lower and middle impoundment (half)**
  - A. Gets all the readily accessible sediment
  - B. Slope transition more gently and natural
  - C. Project limit is located at a more confined setting that is better to let adjust
  - D. Easier to use large wood to hold grade and slowly release material at project limit
4. Lower, middle, and upper impoundment (all)
  - A. Completely eliminate sediment and TP risk
  - B. High per CY impacts for removal in upper impoundment
  - C. Better to leave small amount and let it flow through system over next couple of larger floods





# Alternatives Analysis – Sediment Removal



(MacBroom and Schiff, 2013)



# Alternatives Analysis - Summary

ID	Alternative Description			Objectives				Notes
	Dam	Sediment	Retaining Walls	Reduce flood and erosion risks to nearby property and infrastructure	Naturalize the river and floodplain to improve water quality and habitat	Minimize future maintenance needs	Minimize construction costs	
1	No removal (retain breached structure)	No removal	No removal (retain existing)	NO	NO	NO	YES	Unsafe existing conditions that could be dangerous to nearby property and impact water quality and habitat.
2	Full removal	No removal (allow for passive erosion)	No removal (retain existing)	yes	no	NO	YES	Headcutting and excessive erosion would take place impacting water quality and habitat. Damaged retaining walls would likely fail soon.
3	Full removal	Partial removal (downstream of former bridge abutments)	No removal (retain existing)	YES	no	NO	yes	Sediment erosion will take place at the high-velocity area at the bridge abutments. Walls likely to fail.
4	Full removal	Partial (downstream of former bridge abutments)	Full (replace with slope)	YES	no	yes	yes	Sediment erosion will take place at the high-velocity area at the bridge abutments.
5	Full removal	Partial (downstream of former bridge abutments)	Replace with new wall	YES	no	YES	no	Sediment erosion will take place at the high-velocity area at the bridge abutments.
6	Full removal	Partial removal (downstream of wood jam at RS B+36)	No removal (retain existing)	YES	yes	NO	yes	Good sediment removal option. Walls likely to fail.
7	Full removal	Partial removal (downstream of wood jam at RS B+36)	Full (replace with slope)	YES	yes	YES	yes	Preferred. Removes most of sediment and uses heavy stone slope with joint plantings in place of wall.
7	Full removal	Partial removal - only in channel upstream of abutments (downstream of wood jam at RS B+36)	No removal (retain existing)	YES	yes	NO	yes	Why not remove sediment on floodplain with invasives why in the area? Walls will fail.
	Full removal	Partial removal - only in channel upstream of abutments (downstream and upstream of former bridge abutments)	No removal (retain existing)	YES	yes	NO	yes	Why not remove sediment on floodplain with invasives why in the area? Walls will fail.
8	Full removal	Full removal (downstream and upstream of former bridge abutments)	No removal (retain existing)	YES	yes	NO	yes	Removal of sediment in upper channel seems like it will do more harm than good. No need for extra expense. Walls will fail.
10	Full removal	Full removal (downstream and upstream of former bridge abutments)	Full (replace with slope)	YES	YES	YES	no	Removal of sediment in upper channel seems like it will do more harm than good. No need for extra expense.
11	Full removal	Full removal (downstream and upstream of former bridge abutments)	Replace with new wall	YES	YES	YES	NO	Removal of sediment in upper channel seems like it will do more harm than good. No need for extra expense. Too expensive.



# Connolly Pond Dam Removal - Shrewsbury

Photo-Documentation

Connolly Pond Dam Removal Project, Shrewsbury, Vermont

**Location B, Looking Downstream**

6/19/2023



11/8/2023







# Connolly Pond Dam Removal - Shrewsbury

Photo-Documentation

Connolly Pond Dam Removal Project, Shrewsbury, Vermont

**Location E, Looking Upstream**





# Connolly Pond Dam Removal - Shrewsbury

Photo-Documentation

Connolly Pond Dam Removal Project, Shrewsbury, Vermont

**Location G, Looking West**

6/19/2023





11/8/2023









# Concept Design






# Concept Design



SKETCH CONCEPT PLAN  
CONNOLLY POND DAM REMOVAL  
VNRIC



# Preliminary Design (90%)



## CONNOLLY POND DAM REMOVAL

275 NORTHAM ROAD, TRIBUTARY OF MILL RIVER  
SHREWSBURY, VERMONT

PRELIMINARY DESIGN (90%)  
APRIL 12, 2022



PROJECT SITE VICINITY MAP:



LOCATION MAP:



### PREPARED FOR:

VERMONT NATURAL RESOURCES COUNCIL  
11 BALDWIN STREET  
MONTPELIER, VERMONT 05602



### LIST OF DRAWINGS

NO.	NAME	TITLE
01	—	TITLE SHEET
02	SP-1	SITE PLAN - EXISTING CONDITIONS
03	SP-2	SITE PLAN - PROPOSED CONDITIONS
04	PRD-1	CHANNEL PROFILE
05	STR-1	STRUCTURES REMOVABLE I
06	STR-2	STRUCTURES REMOVABLE II
07	CON-1	CONSTRUCTION ACCESS, SEQUENCE & CONTROL
08	RS-1	SITE PLAN - RESTORATION
09	DET-1	DETAILS

### PREPARED BY:



Know what's below.  
Call before you dig.  
[www.811.com](http://www.811.com)







# Preliminary Design (90%)

## GENERAL NOTES

- THE PURPOSE OF THIS PROJECT IS TO REMOVE CONNOLLY POND DAM ON NORTHAM ROAD IN WESTPORT, VERMONT.
- THE LOCATION OF ALL EXISTING UTILITIES SHOULD BE CONFIRMED PRIOR TO BEGINNING CONSTRUCTION. CALL "DIG SAFE" AT 1-800-GO-DIG (346-7273). THE CONTRACTOR SHALL TAKE PRECAUTIONS NOT TO DISTURB EXISTING UTILITIES.
- THE CONTRACTOR SHALL OBSERVE A SUPERVISOR AT THE START OF CONSTRUCTION AND THE CONTRACTOR'S SUPERVISOR SHALL BE ON SITE AT ALL TIMES THROUGHOUT CONSTRUCTION. THE CONTRACTOR AND HIS/HER SUBS SUPERVISORS SHALL BE RESPONSIBLE FOR COMPLYING WITH THE JOB SAFETY PLAN AND BEST PRACTICES.
- ALL STORAGE AND ACCESS ROUTES, REDSTREAM FENCE BARRIERS, AND LIMITS OF CLEARING SHALL BE PLANNED BY CONTRACTOR PRIOR TO CONSTRUCTION AND APPROVED BY PROJECT ENGINEER.
- WORKING HOLES SHALL BE APPROVED BY PROJECT ENGINEER AND LANDOWNERS.
- NO CONSTRUCTION VEHICLES SHALL BE STREETS, DRIVEWAYS, WALKWAYS OR PAVED IN A LOCATION WHERE LEAKS, SPILLS, WASTE MATERIALS, OILS, OR OTHER LIQUIDS WILL BE INTRODUCED ON TO THE VEHICLE OR WATERCOURSE. AN EMERGENCY MANAGEMENT PLAN AND SPILL KIT WILL BE MAINTAINED ON SITE AT ALL TIMES. IN THE EVENT OF AN ACCIDENTAL RELEASE, IMMEDIATELY STOP CONSTRUCTION WORK.


- CONTAIN THE SPILL AND NOTIFY THE TOWN, APPROPRIATE AGENCIES AND PROJECT ENGINEER. THE SPILL KIT MUST CONTAIN AT A MINIMUM A CONTAINMENT BOOM, STRAW OR OTHER ADEQUATE FILLING, AND ABSORBENT MATERIALS. OILS, WHITE SOLIDS, AND OTHER SPILLS SHOULD BE HANDLED APPROPRIATELY AS TO PREVENT LEACHING OF OILS OR SPILLS INTO STREAMS, WATERCOURSES, OR DRAINAGE. ALL APPROPRIATE STORAGE FOR THESE MATERIALS MUST BE CONTAINED.
- EQUIPMENT SHALL BE REMOVED FROM THE WATERS POND TO REFUELING. NO REFUELING OF EQUIPMENT ALLOWED IN THE WATER.
- ALL EQUIPMENT AND VEHICLES SHALL BE CLEANED PRIOR TO AND FOLLOWING CONSTRUCTION TO REMOVE THE POTENTIAL FOR SPREAD OF PATHOGENS, OILS AND SOLIDS.
- NO TRUCK TRAILS OR OTHER TRACKS. THE CONTRACTOR SHALL MONITOR WEATHER FORECASTS AND STABILIZE THE CONSTRUCTION SITE AND REMOVE EQUIPMENT FROM THE PROJECT AREA TO BE STORED ON DRY GROUND.
- WORK SHOULD BE PERFORMED DURING LOW WATER.
- TRUCKS SHALL BE NO CLAMS FOR EXTRA COMPENSATION DUE TO DELAYS IN WATER CONTROL ASSOCIATED WITH HIGH WATER LEVELS FROM

- NATURAL EVENTS SUCH AS FLOODS.
- THE CONTRACTOR SHALL MAINTAIN ALL ROADWAYS, SIDEWALKS, AND UTILITIES IN THE AREA PRIOR TO, DURING AND THROUGHOUT CONSTRUCTION. CONSTRUCTION ACTIVITIES MUST BE MAINTAINED AT EACH SITE ACCESS POINT. SEE PLANS AND DETAILS.
- CONTRACTOR MUST COMPLY WITH ALL APPLICABLE FEDERAL, STATE AND LOCAL PERMITS THROUGHOUT DURATION OF PROJECT.
- ALL CONCRETE AND REINFORCING STEEL IS TO BE REMOVED FROM WASTE AND DISPOSED OF OR RECYCLED OFF SITE.
- PERSONNEL, MATERIALS, AND OTHER EQUIPMENT ARE TO BE STAYED BY THE CONTRACTOR AND FENCED BY THE PROJECT ENGINEER. FINAL DETERMINATION WILL BE PROVIDED BY THE OWNER BY THE PROJECT ENGINEER.
- NO BACKLOG PERMITS IS NOT PROVIDED. DO NOT REMOVE BACKLOG WITHOUT DIRECTION OF PROJECT ENGINEER.
- ALL MATERIALS, EQUIPMENT, OR OTHER SHALL BE LEGALLY DISPOSED OF IN AN UPWARD LOCATION AT NO ADDITIONAL COST. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING A SUFFICIENT RECEIPT OF THE MATERIALS, GAINING REGULATORY APPROVAL FOR EXPOSED MATERIAL PLACEMENT IF NECESSARY, AND MAINTAINING.

- ## OPERATION AND MAINTENANCE NOTES
- SOIL CONDITIONS ARE DETERMINED TO AVOID OTHER DRAINAGE EQUIPMENT TO ALLOW THE STREAM TO MAINTAIN OVER TIME. THE CHANNEL WILL MOVE IN THE FUTURE.
  - PLANTED VEGETATION IS TO BE MAINTAINED DURING THE GROWING SEASON FOR TWO YEARS TO MAINTAIN A SUCCESSFUL VEGETATION ESTABLISHMENT. OF ANNUAL COVERAGE.
  - ANY AREAS OF POOR VEGETATIVE COVER SHALL BE REPLANTED ACCORDINGLY.

## SEDIMENT MANAGEMENT NOTES

- EXISTING SEDIMENT ACCUMULATED BEHIND DAM + 4,000 CY OF BULKY SOIL CY ARE ESTIMATED TO REMOVED DURING POST DAM REMOVAL. EXPECTED RECONSTRUCTION VOLUME IS +1,000 CY OVER A CHANNEL LENGTH OF 100' BEHIND DAM. SEDIMENT EXTRACTED TO NATURALLY FORM DRAINAGE OR STABILIZE IN PLACE.
- PILOT CHANNEL CONCEPTS WILL FOLLOW THE TYPICAL CROSS SECTION WITH DIRECTION OF FLOW FROM CHANNEL AND CHANNEL DEEPENED TO FORM BASE WITHIN THE STUDY CHANNEL.
- STOCKPILE NATURAL STREAM CHANNEL, LOGS, AND BRIDGES TO REBUILD CHANNEL.
- STOCKPILE LOGS 1.5' AND 1.875' AND LOGS OR STUMPS FOR REUSE AS CHANNEL ROUGHNESS ELEMENTS WHEN RESTORING CHANNEL BED.
- TRUCKS CARRIED ON LOGS RESTORED IN SEQUENCE TO BE REINSTALLED IN CHANNEL OF LOGS DAM.



DATE	BY	REVISIONS

**SITE PLAN - PROPOSED CONDITIONS**  
**CONNOLLY POND DAM REMOVAL**  
 270 NORTHAM ROAD, TOWN OF WESTPORT, VERMONT  
 PRELIMINARY DESIGN

RWS	DATE	RWS

1" = 40'  
 APRIL 12, 2022  
 16304.0000  
 3 OF 8

**SP-2**









# Preliminary Design (90%)

### TRAFFIC MANAGEMENT NOTES

1. ALL TEMPORARY TRAFFIC CONTROL WORK SHALL COMPLY TO THE LATEST EDITION OF THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".
2. ALL SIGN LEGENDS, BARRELS, AND POSTING SHALL BE IN ACCORDANCE WITH THE NOTES.
3. ALL CONSTRUCTION SIGNS SHALL BE IN PLACE PRIOR TO THE COMMENCEMENT OF WORK.
4. ALL SIGNS SHALL BE MOUNTED ON THEIR OWN STANDARD SIGN SUPPORTS.

### EROSION CONTROL NOTES

1. THE SEDIMENT AND EROSION CONTROL PRACTICES IMPLEMENTED AS PART OF THE PROJECT SHALL BE IMPLEMENTED AND MAINTAINED ACCORDING TO THE LOW EROSION TECHNIQUES FOR EROSION PREVENTION AND SEDIMENT CONTROL GUIDANCE DOCUMENT FROM THE VERMONT DEPARTMENT OF ENVIRONMENTAL CONSERVATION, WHICH APPLIES IN CONSULTATION WITH PROJECT ENGINEER.
2. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE JOB SITE.
3. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE MAINTAINED ON THE JOB SITE.
4. ALL SOIL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE INSTALLED PRIOR TO ANY MAJOR DISTURBANCE OF THE EARTH'S SURFACE, AND MAINTAINED UNTIL PERMANENT RESTORATION IS ESTABLISHED.
5. THE CONTRACTOR IS RESPONSIBLE FOR THE MAINTENANCE OF ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES. THE CONTRACTOR WILL VERIFY THE MAINTENANCE WEEKLY AND AFTER RAIN EVENTS AND REPORT TO WRITING TO PROJECT ENGINEER.
6. THE PROJECT ENGINEER IS TO BE NOTIFIED IMMEDIATELY IF EXCESSIVE SEDIMENT OCCURS. PLACE A STOP SIGN FOR EXCESSIVE SEDIMENT TO BE STOPPED OR STOPPED FOR EXCESSIVE SEDIMENT.
7. REMOVE HIGH DRAINAGE LOW FLOW VEGETATION IF A LARGE FLOOD IS PREDICTED. STOP WORK UNTIL THE JOB AND EROSION CONTROL FROM FLOOD PROTECTION.
8. STOPPAGE AND STAGING LOCATIONS AS INDICATED ON THE PLAN AND AS APPROVED BY THE PROJECT ENGINEER, SHALL BE MAINTAINED WITHIN THE LIMIT OF DISTURBANCE, WITHIN THE OUTSIDE OF THE PROJECT AREA SHALL BE PROTECTED AND REMAIN UNDISTURBED THROUGHOUT THE DURATION OF THE PROJECT.
9. NO DISTURBED EARTH WILL BE OPEN EXPOSED FOR MORE THAN 90 DAYS (7) CONSECUTIVE DAYS WITHOUT APPLYING TEMPORARY OR PERMANENT STABILIZATION MEASURES AT THE END OF THE EXPOSED AREA SHALL BE SEEDING AND MULCHED OR PROTECTED WITH EROSION CONTROL MATTING WITHIN 90 DAYS OF WORKING FROM CHANGE.
10. ANY DISTURBED SLOPE 2:1 OR STEEPER SHALL BE STABILIZED WITH EROSION CONTROL BLANKET OR VEGETATION WITHIN 90 DAYS.

### INVASIVE SPECIES HANDLING NOTES

1. THESE NOTES PROVIDE BEST MANAGEMENT PRACTICES FOR PREVENTING THE SPREAD OF INVASIVE SPECIES. ADDITIONAL INFORMATION ON IDENTIFICATION AND IDENTIFICATION OF INVASIVE SPECIES CAN BE FOUND AT WWW.CITIZENSUS.ORG
2. LOCATE AND USE EXISTING AREAS THAT ARE FREE OF INVASIVE SPECIES TO AVOID SPREADING SEEDS AND OTHER VIABLE PLANT PARTS.
3. PLAN WORK SEQUENCES TO AVOID SPREADING SEEDS TO ADJACENT AREAS. INVASIVE SPECIES SEEDS ARE ALREADY PRESENT IN THE AREA. SEEDS SHOULD BE CLEANED OF ALL SEEDS WITHIN THE AREA ALREADY IMPACTED. ACCEPTABLE CLEANING METHODS INCLUDE:
  - 4.1. PORTABLE WASH STATION THAT CONTAINS SEEDS FROM WASHED EQUIPMENT
  - 4.2. HIGH PRESSURE AIR
  - 4.3. HIGH PRESSURE WATER
  - 4.4. HIGH PRESSURE AIR OR WATER
- 4.5. EQUIPPED WATER, TAKEN FROM SITES THAT CONTAIN INVASIVE PLANTS CANNOT BE AWAY FROM THE SITE OF INVESTIGATION UNTIL ALL VIABLE PLANT MATERIAL IS REMOVED NON-VIABLE. EXCAVATED MATERIAL MAY BE REUSED WITHIN THE EXACT LIMITS OF THE PROJECT.
5. ANY EXTRA EXCAVATED MATERIAL, CONTAINING INVASIVE PLANT MATERIAL, MUST BE STOCKPILED ON AN IMPERVIOUS SURFACE UNTIL 72 HOURS AFTER THE DISTURBANCE IS COMPLETED BY WHICH TIME BEST PRACTICE SHOULD BE IMPLEMENTED AND KNOWN TO BE 3 FEET FROM OTHER SPECIES.
6. SOIL AND OTHER MATERIALS CONTAINING INVASIVE PLANT MATERIAL MUST BE COVERED DURING TRANSPORT.
7. INVASIVE SPECIES CAN BE REMOVED MONITORABLE BY THE FOLLOWING METHODS:
  - 8.1. BURNING MONITORABLE AREAS THAT ARE NOT SETTING OR FLOWING IS ACCEPTABLE. BURNED MATERIAL SHOULD BE TAKEN TO A DESIGNATED BURN AREA. MAKE SURE THAT ANY REMAINING ROOTS OR ROOT FRAGMENTS ARE NON-VIABLE. OBTAIN ALL NECESSARY PERMITS BEFORE BURNING.
  - 8.2. BURNING MONITORABLE AREAS IS ACCEPTABLE. BURNED SEEDS SUCH AS AMARANTH KNIGHTS SHOULD BE BURNED AT LEAST 3 FEET AND BURNED MATERIAL MUST BE REMOVED OR BURIED ON TOP OF THE EXISTING SITE.
  - 8.3. MANUAL REMOVAL BY A LICENSED SPECIALIST OR WELL-TRAINED FIELD OPERATOR IS ACCEPTABLE.
8. INVASIVE SPECIES INCLUDING INSECTS, AND OTHER INVASIVE SPECIES WILL BE MONITORED BY OTHERS CONCURRENTLY WITH THE BEST MANAGEMENT PRACTICES AND AN OBSERVATION RECORD SHOULD BE MAINTAINED WITH THE ASCE REPORT.

### WATER CONTROL PLAN

THE PROPOSED DAM REMOVAL IS PROVIDED AS A RECOMMENDED APPROACH TO DRAINAGE THE WORK AREA TO MAINTAIN THE RELEASE OF SEDIMENT. THE CONTRACTOR IS RESPONSIBLE FOR SUBMITTING A PROPOSED WATER CONTROL PLAN TO THE STATE OF VERMONT FOR APPROVAL PRIOR TO THE START OF CONSTRUCTION.

1. DESIGN A SCHEDULED SEDIMENT AND EROSION CONTROL PLAN, CONSTRUCTION SEQUENCE, AND WATER CONTROL PLAN TO THE PROJECT ENGINEER FOR REVIEW PRIOR TO START OF CONSTRUCTION.
2. OBTAIN ANY NECESSARY WORK PERMITS AND NEIGHBORHOOD PLANS, AND PROJECT REGISTRATION, INCLUDING THE ENVIRONMENTAL PROTECTION PLAN TO THE PROJECT ENGINEER.
3. CONTRACTOR SHALL PARTICIPATE IN A PRE-CONSTRUCTION SITE WALK WITH THE PROJECT ENGINEER AND OTHERS TO REVIEW ENVIRONMENTAL, HAZARD EVALUATION, CONTACT PROVISIONS, PROJECT LIMITS, AND CONSTRUCTION SEQUENCES.

### CONSTRUCTION SEQUENCE NOTES

THE PROPOSED DAM REMOVAL SEQUENCE IS PROVIDED AS A RECOMMENDED APPROACH. THE CONTRACTOR IS RESPONSIBLE FOR SUBMITTING A PROPOSED SEQUENCE TO THE PROJECT ENGINEER FOR APPROVAL PRIOR TO THE START OF CONSTRUCTION.

- STEP A: PRE-CONSTRUCTION ACTIVITIES**
  1. SUBMIT A SCHEDULED SEDIMENT AND EROSION CONTROL PLAN, CONSTRUCTION SEQUENCE, AND WATER CONTROL PLAN TO THE PROJECT ENGINEER FOR REVIEW PRIOR TO START OF CONSTRUCTION.
  2. OBTAIN ANY NECESSARY WORK PERMITS AND NEIGHBORHOOD PLANS, AND PROJECT REGISTRATION, INCLUDING THE ENVIRONMENTAL PROTECTION PLAN TO THE PROJECT ENGINEER.
  3. CONTRACTOR SHALL PARTICIPATE IN A PRE-CONSTRUCTION SITE WALK WITH THE PROJECT ENGINEER AND OTHERS TO REVIEW ENVIRONMENTAL, HAZARD EVALUATION, CONTACT PROVISIONS, PROJECT LIMITS, AND CONSTRUCTION SEQUENCES.
- STEP B: CONSTRUCTION SETUP ACTIVITIES**
  1. INSTALL CONSTRUCTION WARNING SIGNS AND SAFETY FENCING, INSTANT TRAFFIC CONTROL, AS REQUIRED.
  2. STAKE OUT LIMITS OF WORK AND INSTALL SEDIMENT AND EROSION CONTROL MEASURES PERMITTED TEMPORARY ACCESS, STAGING AND STORAGE AREAS.
  3. WAIT FOR LOW FLOOD TO BEGIN IN CHANNEL WORK.
- STEP C: STONE CHECK DAM AND TREE REMOVAL**
  1. INSTALL STONE CHECK DAM (SEE DETAIL), ON APPROXIMATE EQUAL, PRIOR TO CONSTRUCTION.
  2. REMOVE STONE CHECK DAM AND REMOVE CONSTRUCTION.
  3. REMOVE ACCUMULATED SEDIMENT REGULARLY, ONCE PRACTICES CAN ACCESS AREA.
  4. REMOVE TREE FROM DAM EMBRACEMENT.
- STEP D: DAM EMBRACEMENT CUT AND FILL**
  1. REMOVE EXISTING DAM AND STOCKPILE FOR TOWN.
  2. EXCAVATE DAM EMBRACEMENT AND USE REMOVED MATERIAL TO FILL DESIGNATED AREAS. SEE SHEET FRS FOR DAM ELEVATION.
  3. ESTABLISH SHOULDER CHANNELS THROUGH FILL AREA ON EAST SIDE OF RIDGE.
- STEP E: CHANNEL RESTORATION AND SEDIMENT REMOVAL**
  1. INCREMENTALLY EXPOSE DAM ALTERNATING WITH REMOVED SEDIMENT THROUGH CHANNEL RESTORATION.
  2. REMOVE SEDIMENT FROM LOWER PROHIBITION. SPREAD REMOVED FINE SEDIMENT ON FILL SLOPES AS TOP SOIL.
  3. ESTABLISH PILOT CHANNEL THROUGH LOWER PROHIBITION.
  4. INSTALL REMOVED TREES WITH ROOT BALLS AND SOIL BODIES IN PROPOSED TRAIL CHANNEL AS SOON AS PROPOSED CHANNEL IS EXCAVATED.
- STEP F: CHANNEL RESTORATION THROUGH DAM EMBRACEMENT TO TOWN CANAL, REMOVE AND REPAIR OF EXISTING STRUCTURES**
  1. COMPLETE CHANNEL EXCAVATION THROUGH DAM EMBRACEMENT TO TOWN CANAL, REMOVE AND REPAIR OF EXISTING STRUCTURES.
  2. REMOVE STONE CHECK DAM.
- STEP G: POST-CONSTRUCTION ACTIVITIES**
  1. PREPARE SITE RECOVERY: REMOVE ALL EXCESS ROADS AND CONSTRUCTION INFRASTRUCTURE, AND STABILIZE AND RESTORE ALL DISTURBED AREAS. COMPLETE SITE RESTORATION, BEFORE TO ORIGINAL CONDITION, OR AS NEAR TO IT AS THE USE OF CONSTRUCTION SITE WALK WITH PROJECT ENGINEER.

### LEGEND

- PROPOSED EDGE OF WATER
- EXISTING IN-PLACE CONTOUR
- EXISTING FINDER CONTOUR
- APPROX. PROPERTY LINE
- EXISTING TREE LINE
- DESIGNATED HIGH WATER
- LIMITS OF FORMER PROHIBITION

DATE	BY	DESCRIPTION

**CONSTRUCTION ACCESS, RESTORATION & CONTROL**

**CANNONVILLE POND DAM REMOVAL**

3700 NORTH MAIN ROAD, TOWN OF HILL, VERMONT  
PROJECT NUMBER: 2023-000001

DATE	BY	REVISION

SCALE: 1" = 40'

DATE: APRIL 12, 2022

PROJECT NUMBER: 2023-000001

PAGE: 1 OF 8

**CON-1**









# Record Drawing



## CONNOLLY POND DAM REMOVAL

275 NORTHAM ROAD, TRIBUTARY OF MILL RIVER  
SHREWSBURY, VERMONT

FINAL DESIGN  
JULY 26, 2022  
REVISED SEPTEMBER 26, 2022  
RECORD DRAWING FEBRUARY 5, 2023

POST-CONSTRUCTION CONDITIONS  
DENOTED IN RED

### CONSTRUCTION INFORMATION

CONSTRUCTION COMPLETED BY:  
EROSIVE SLOPE WORK  
CONSTRUCTION OVERSIGHT BY:  
SLR CONSULTING  
CONSTRUCTION PROJECT MANAGEMENT BY:  
VERMONT NATURAL RESOURCES COUNCIL



PROJECT SITE VICINITY MAP:



LOCATION MAP:



PREPARED FOR:  
VERMONT NATURAL RESOURCES COUNCIL  
11 BALDWIN STREET  
MONTPELIER, VERMONT 05602



### LIST OF DRAWINGS

NO.	NAME	TITLE
01	---	TITLE SHEET
02	SP-1	SITE PLAN - EXISTING CONDITIONS
03	SP-2	SITE PLAN - PROPOSED CONDITIONS
04	PRD-1	CHANNEL PROFILE AND CROSS SECTION
05	STR-1	STRUCTURE REMOVALS I
06	STR-2	STRUCTURE REMOVALS II
07	CON-1	CONSTRUCTION ACCESS, SEQUENCE & CONTROL
08	RE-1	SITE PLAN - RESTORATION
09	DET-1	SITE PLAN - DISTURBED AREAS
10	DET-1	DETAILS

PREPARED BY:



SLR CONSULTING  
100 NORTH MAIN STREET  
SHREWSBURY, VT 05485  
WWW.SLRCONSULTING.COM




Know what's below.  
Call before you dig.  
www.digv.com








# Record Drawing





# Complex Design – Dunklee Pond Dam Removal



### GENERAL NOTES



1. THE PURPOSE OF THIS PROJECT IS TO REMOVE DUNKLEE POND DAM ON TRUNK ROAD IN BUTLICK TOWNSHIP, PROVIDING FOR IMPROVED FLOOD CONTROL, WATER QUALITY AND AQUATIC ECOSYSTEM RESTORATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
2. THE LOCATION OF ALL EXISTING UTILITIES SHOULD BE CONFIRMED PRIOR TO BEGINNING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
3. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL ADJACENT PROPERTIES THROUGHOUT CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
4. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL ADJACENT PROPERTIES THROUGHOUT CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
5. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL ADJACENT PROPERTIES THROUGHOUT CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
6. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL ADJACENT PROPERTIES THROUGHOUT CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
7. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL ADJACENT PROPERTIES THROUGHOUT CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
8. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL ADJACENT PROPERTIES THROUGHOUT CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
9. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL ADJACENT PROPERTIES THROUGHOUT CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
10. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL ADJACENT PROPERTIES THROUGHOUT CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.

### SITE RECOVERY NOTES

1. REMOVE TEMPORARY ACCESS RAMP AND TEMPORARY STOCKPILE AREAS.
2. RESTORE ALL ACCESS ROUTES USING DRAINAGE CONSTRUCTION TO THE EXISTING OR IMPROVED CONDITION. FILL RUTS CREATED BY EQUIPMENT TO RESTORE GRADE AND REVEGETATE AS NOTED.
3. CONTRACTOR IS RESPONSIBLE FOR REMEDIAL WORK, PARKING AREAS, SIDEWALKS, AND CURBS OF GARAGES BY CONSTRUCTION ACTIVITIES.
4. RESTORE ALL OTHER DISTURBED AREAS WITHIN THE PROJECT SITE SUCH AS TEMPORARY ACCESS ROADS, STOCKPILE AREAS, STAGING AREAS, AND BARBED WIRE AREAS TO ORIGINAL OR IMPROVED CONDITION.
5. ALL PLANT MATERIALS SHALL BE PLANTED AT THE SAME DENSITY AS THE ORIGINAL PLANTING. PLANTING SHALL BE DONE BY THE CONTRACTOR. PLANTING SHALL BE DONE BY THE CONTRACTOR. PLANTING SHALL BE DONE BY THE CONTRACTOR.
6. REMOVE TEMPORARY ACCESS RAMP AND TEMPORARY STOCKPILE AREAS.
7. RESTORE ALL ACCESS ROUTES USING DRAINAGE CONSTRUCTION TO THE EXISTING OR IMPROVED CONDITION. FILL RUTS CREATED BY EQUIPMENT TO RESTORE GRADE AND REVEGETATE AS NOTED.
8. CONTRACTOR IS RESPONSIBLE FOR REMEDIAL WORK, PARKING AREAS, SIDEWALKS, AND CURBS OF GARAGES BY CONSTRUCTION ACTIVITIES.
9. RESTORE ALL OTHER DISTURBED AREAS WITHIN THE PROJECT SITE SUCH AS TEMPORARY ACCESS ROADS, STOCKPILE AREAS, STAGING AREAS, AND BARBED WIRE AREAS TO ORIGINAL OR IMPROVED CONDITION.
10. ALL PLANT MATERIALS SHALL BE PLANTED AT THE SAME DENSITY AS THE ORIGINAL PLANTING. PLANTING SHALL BE DONE BY THE CONTRACTOR. PLANTING SHALL BE DONE BY THE CONTRACTOR.




# Complex Design – Longitudinal Profile







# Complex Design – Stabilize Section





# Design Demystified





# Design Demystified



VIEW LOOKING EAST



One Year Post-construction

(Source: SLR)



# Final Design (100%)




## GROTON ROAD BRIDGE REPLACEMENT

LITTLE ITALY ROAD OVER KEENAN BROOK  
GROTON, VERMONT

SLR PROJECT NO. 14655.00010  
DECEMBER 03, 2024



PROJECT SITE VICINITY MAP.



LOCATION MAP:



### PREPARED FOR:

CALCEONIA COUNTY INC  
481 SUMMER STREET SUITE 202  
ST. JOHNSBURY, VERMONT 05819

### LIST OF DRAWINGS

NO.	NAME	TITLE
01		TITLE SHEET
02	EX-1C	ROAD BRIDGE EXISTING CONDITIONS
03	SP-1C	ROAD BRIDGE SITE PLAN
04	PR-1C	ROAD BRIDGE STRUCTURE PROFILES
05	PR-2C	KEENAN BROOK CHANNEL PROFILE FOR ROAD BRIDGE
06	COA-1C	ROAD BRIDGE STAGED CONSTRUCTION PLAN
07	BR-1C	BORING LOGS
08	STR-1C	ROAD BRIDGE STRUCTURAL PLAN & ELEVATION
09	STR-2C	ROAD BRIDGE ABUTMENT PLAN & ELEVATION
10	STR-3C	ROAD BRIDGE STRUCTURAL DETAILS
11	STR-4C	ROAD BRIDGE STRUCTURAL DETAILS
12	STR-5C	ROAD BRIDGE STRUCTURAL DETAILS
13	DET-1C	ROAD BRIDGE DETAILS

### PREPARED BY:












# Final Design (100%)






# Final Design (100%)



**KEENAN BROOK EXISTING CHANNEL PROFILE**  
SCALE: 1" = 20' (H), 1" = 5' (V)




**KEENAN BROOK PROPOSED CHANNEL PROFILE**  
SCALE: 1" = 20' (H), 1" = 5' (V)







# Final Design (100%)



- GENERAL NOTES**
- THE PLANS REQUIRE A CONTRACTOR'S WORKING KNOWLEDGE OF LOCAL, MUNICIPAL, AND STATE CODES FOR UTILITY SYSTEMS. ANY CONFLICTS BETWEEN MATERIALS AND LOCATIONS SHOWN, AND LOCAL REQUIREMENTS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO THE EXECUTION OF WORK. THE ENGINEER WILL NOT BE HELD LIABLE FOR COSTS INCURRED TO IMPLEMENT OR CORRECT WORK WHICH DOES NOT CONFORM TO LOCAL CODE.
  - ALL FILL, OIL, PAINT, OR OTHER HAZARDOUS MATERIALS SHOULD BE STORED IN A SECONDARY CONTAINER AND REMOVED TO A LICENSED DUMP OR AREA WITH AN IMPERVIOUS FLOOR DURING NON-WORK HOURS.
  - ALL PROPOSED CONTOURS AND SPOT ELEVATIONS INDICATE FINISHED GRADE.

- STRUCTURAL NOTES**
- SPECIFICATIONS: VERMONT STATE DEPARTMENT OF TRANSPORTATION SPECIFICATIONS, DATED 2024.
  - DESIGN SPECIFICATIONS: STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES (ASPH/PTLPS, 9TH EDITION, 2020) WITH INTERIM SPECIFICATIONS UP TO AND INCLUDING 2026, AS SUPPLEMENTED BY THE VERMONT STATE DEPARTMENT OF TRANSPORTATION BRIDGE DESIGN MANUAL.
  - ALLOWABLE DESIGN STRESSES:  
CLASS 70F  $F_t = 4,000$  PSI (CONTRACTOR TO SUBMIT HEX DESIGN FOR APPROVAL)
  - REINFORCEMENT:  
ASTM A615 GRADE 60  $F_y = 60,000$  PSI
  - MIN. LIVE LOAD: HL-93
  - CONCRETE: WHEN DECIMAL DIMENSIONS ARE GIVEN TO LESS THAN THREE DECIMAL PLACES, THE OMITTED DIGITS SHALL BE ASSUMED TO BE ZEROS.
  - EXISTING DIMENSIONS: DIMENSIONS OF THE EXISTING STRUCTURE SHOWN ON THESE PLANS ARE FOR GENERAL REFERENCE ONLY AND ARE NOT GUARANTEED. THE CONTRACTOR SHALL TAKE ALL FIELD MEASUREMENTS NECESSARY TO ASSURE PROPER FIT OF THE PROPOSED WORK AND SHALL ASSUME FULL RESPONSIBILITY OF THEIR ACCURACY. WHEN SHOP DRAWINGS BASED ON FIELD MEASUREMENTS ARE SUBMITTED FOR APPROVAL, THE FIELD MEASUREMENTS SHALL ALSO BE SUBMITTED FOR REFERENCE BY THE REVIEWER.

- CONCRETE NOTES**
- REMAIN-IN-PLACE FORMS: THE USE OF REMAIN-IN-PLACE FORMS ON THIS STRUCTURE IS NOT ALLOWED.
  - CLASS 70F CONCRETE: CLASS 70F CONCRETE SHALL BE USED FOR THE BRIDGE ABUTMENTS.
  - CONCRETE COVER: ALL REINFORCEMENT SHALL HAVE TWO INCHES OF COVER UNLESS DIMENSIONED OTHERWISE.
  - EXPOSED EDGES: EXPOSED EDGES OF CONCRETE SHALL BE FINISHED 1/4" UNLESS DIMENSIONED OTHERWISE.
  - REINFORCEMENT: ALL REINFORCEMENT SHALL BE ASTM A615 GRADE 60.
  - EPOXY COATED REINFORCING BARS: ALL REINFORCEMENT WITHIN THE ABUTMENTS SHALL BE EPOXY COATED AND SHALL BE INCLUDED IN THE PAY ITEM.
  - CONCRETE DISPOSAL: CONCRETE IS NOT TO BE DISPOSED ON SITE.




**SLR**  
SLOAN CONSULTANTS, INC.  
REGISTERED PROFESSIONAL ENGINEERS  
VERMONT

PROJECT NO. 2024-001  
DATE: 12/20/24  
SCALE: 1/4" = 1'-0"


ROAD BRIDGE STRUCTURAL PLANS & ELEVATION  
LITTLE ITALY ROAD OVER VERMONT BROOK  
BRIDGE REPLACEMENT

REV. NO. REV. DATE  
AS NOTED  
DECEMBER 21, 2024  
1804 00010  
18 OF 17

**STR-1C**



# Final Design (100%)














# Design Demystified





# Design Demystified





# Design Recommendations

- Match the number of design levels to the complexity of the project, addressing all constraints.
- Naturalize channel morphology.
- Establish early communications with the landowner, abutters, and community.
- Share information with regulators prior to seeking permits.
- Be flexible to make field changes as new information becomes available during project.
- Form a cohesive project team to successfully design and build a project.



Thank You

