

# **Reconnecting Waterways**

## **Understanding State Permitting for Culvert Replacement and Dam Removal**

**VT DEC Watershed Management**

**Rivers Program – River Management Section**

December 2024

# Topics to Discuss – Presentation Agenda

## **Regulated Streams**

Jurisdiction and Technical Guidance

Definition and Field Characteristics

Intermittent Streams and the MRGP

## **Other State Regulatory Requirements**

## **Stream Crossing Structure Replacement**

Design Standards

Construction Plans

Inspection Frequency

## **Dam Removals and Stream Restoration**

Design Standards

Phasing and Sequencing Plans

Dewatering and Flow Controls

Inspection Frequency

# List of Bureaucratic Acronyms

Vermont Department of Environmental Conservation (VT DEC)

Flood Hazard Areas and River Corridor (FHARC)

Municipal Road General Permit (MRGP)

Stormwater Construction General Permit (CGP)

Stream Alteration General Permit (SAGP)

Wetlands Non-Reporting General Permit (NRGP)

Active Channel Width (ACW)

Bankfull Channel Width (Wbkf)

Bankfull Channel Depth (Dbkf)

Environmental Stone, i.e. placed stream bed material (E-stone)

**Jurisdiction of the VT DEC Stream Alteration  
General Permit (SAGP)**

# Jurisdiction of the Stream Alteration General Permit

## B.1 Definitions

(38) “Perennial stream” means a watercourse or portion, segment, or reach of a watercourse, generally exceeding 0.5 square miles in watershed size, in which surface flows are not frequently or consistently interrupted during normal seasonal low flow periods. Perennial streams that begin flowing subsurface during low flow periods, due to natural geologic conditions, remain defined as perennial. All other streams, or stream segments of significant length, shall be termed intermittent. A perennial stream shall not include the standing waters in wetlands, lakes, and ponds.

B.2. Jurisdictional Limits B.2.2. Within Watercourses - A person shall not change, alter, or modify the course, current, or cross section of any watercourse or of any designated outstanding resource waters, within or along the boundaries of this State either by movement, fill, or by excavation of ten cubic yards or more of material in any year, unless authorized by the Secretary. A watercourse is any perennial stream.

# Technical Guidance for Identification of Perennial Streams For the Purpose of Jurisdictional Determinations Under 10 VSA Section 1021(a) and 1002(10)

Definition of Perennial Stream - A perennial stream is a watercourse, or portion, segment or reach of a watercourse that, in the absence of abnormal, extended or severe drought, continuously conveys surface water flow. Human caused interruptions of flow; i.e. flow fluctuations associated with hydroelectric facility operations, or water withdrawals, shall not influence the determination. A perennial stream shall not include the standing waters of wetlands, lakes, and ponds.

All other streams or portions thereof shall be considered and termed intermittent. A stream may, along its course, cycle from intermittent to perennial to intermittent through multiple iterations

**What does this all really mean? Call the regional River Management Engineer!**

# Technical Guidance for Identification of Perennial Streams

## Evaluative Parameters

A perennial stream may be characterized by any of the following:

1. Direct observation or compelling evidence obtained that surface flow is uninterrupted.
2. Presence of one or more geomorphic characteristics typically associated with perennial streams including:
  - a. Bed forms; i.e. riffles, pools, runs, gravel bars, other depositional features, bed armor layer
  - b. Bank erosion and/or bed scour
  - c. Indications of waterborne debris and sediment transport
  - d. Defined bed and banks.
3. Watershed size greater than 0.25 square miles.
4. VHD data layer-derived application of USGS regression for intermittent stream flow probability.
5. Presence of aquatic organisms requiring uninterrupted flow for survival.
6. Base flows are primarily supported by groundwater recharge as indicated by bank seeps, springs or other indicators.
7. Presence of highly permeable channel (particularly streambed) boundary conditions in conjunction with occasional to frequent decline of the groundwater table below the streambed elevation.
8. Surrounding topography exhibits characteristics of being formed by fluvial processes.



# What is a Perennial Stream?

A reach or segment of a stream in which surface flows are not frequently or consistently interrupted during seasonal, low flow periods; and supports aquatic life (not just fish!)



Wild brook trout collected from Heartwellville Brook.





**What about Intermittent Stream Channels?**

# What is an Intermittent Stream Channel

## Intermittent Streams:

A seasonal stream channel which flows for part of the year

Still has a defined bed and bank, sediment and debris transport

May support aquatic organisms including resident fish populations

NOT regulated under the SAGP since they are not perennial, these stream channels are jurisdictional under the VT DEC Municipal Roads General Permit (MRGP); focused on reducing stormwater related erosion on municipalities roads

**Sizing of replacement structures is based on ACTIVE CHANNEL WIDTH (ACW);**  
scour line along bottom of bank similar to USACE Ordinary High Water (OHW)

# Intermittent Streams – Municipal Culvert Sizing under MRGP using Active Channel Width (ACW)





Figure IX-3. Active channel width versus bankfull channel width.



Figure IX-4. Example of active and bankfull channel margin.






# Intermittent Stream Culvert Designs for Municipalities

## INTERMITTENT STREAM CROSSINGS:

- Match long slope of the stream channel when setting slope of the new crossing structure
- Minimum pipe embedment (20-30% of rise) or 1-1.5 feet below the long bed slope
- Select pipe shape based on road height, i.e. benefits of round vs squashed culvert
- No infill with ANR E-stone due to height restrictions, assumed accumulation of sediment in culvert with DS grade controls installed
- Reference Appendix C of VT DEC MRGP



# **Other State Permits for Barrier Removal Projects**





# Permits for Culvert and Bridge Replacement Projects

## VT DEC Stream Alteration General Permit (SAGP)

General Permit – most projects in compliance with the performance standards are processed as a “Registration”, higher risk projects are processed as “Applications”

## VT DEC State Wetlands Permit

Allowed Use – a one-time expansion of 250 sf beyond the maintained road prism

Non-reporting General Permit (NRGP) – up to 1,000 sf of permanent impacts to wetlands and buffers with up to 5,000 sf of temporary impacts for access/reroutes

## Municipal bylaws under National Flood Insurance Program (NFIP)

In Special Flood Hazard Area (SFHA) – upsizing culverts and bridges in FEMA mapped floodplains often triggers a local review by the Town zoning or planning commission

# Permits for Dam Removal and Restoration Projects

## **VT DEC Stream Alteration General Permit (SAGP)**

General Permit – more complex or higher risk projects processed as ‘Applications’ which include a 14-day public notice period, posting on the Environmental Notice Bulletin (ENB)

Individual Permit (IP) – projects with post-construction monitoring requirements for either water quality, channel evolution, or sediment transport concerns; 30-day posting to ENB

## **VT DEC State Wetlands Permit**

Allowed Use – stream restoration plan is reviewed and approved by Wetland Biologist

General Permit (GP) – placement of fill within a regulated wetland or its buffer often triggers the need for a permit; including temporary construction access and stockpiles. Access routes/haul roads placed on timber mats or temporary road within the excavation footprint of impounded sediments are excluded; 14-day public notice period on ENB

*\* disposal of sediments in a wetland, floodplain, or river corridor is rarely approved*

# Permits for Dam Removal and Restoration Projects

*continued*

## **VT DEC Dam Safety Program (DSP)**

Dam Safety Order (DSO) – jurisdiction over the removal of dams which are non-power, non-federal dams with water/sediment impoundment volume of 500k cubic feet or more

## **VT DEC Stormwater Program**

Construction General Permit (CGP) – jurisdiction when there is 1 acre or more of soil disturbance beyond the 2-year flood inundation limits behind the dam impoundment; calculate area of haul roads, cleared and staging-laydown areas, disposal sites, etc...)

## **VT DEC Lakes and Ponds**

Lake Encroachment – jurisdiction over FERC hydroelectric dams, DSP dams are Exempt  
Shoreline Protection - jurisdiction over the creation of new impervious surface and new cleared area within 250 feet of the mean water level (not typical for dam removals)

# Permits for Dam Removal and Restoration Projects

*continued*

## **Flood Hazard Areas and River Corridor General Permit**

FHARC GP - jurisdiction over activities which are exempt from municipal regulations, i.e. state-owned and operated institutions and facilities; review by DEC Floodplain Manager

## **State Transportation Projects under Title 19**

Stream Crossings - consultation with RME on design plans satisfying SAGP standards

Dam Removal - likely jurisdictional under both DSP and SAGP due to extent of stream restoration outside of state ROW; same design standards as a regular dam removal

## **Natural Resource Board (NRB) Act 250**

Criterion 1D Floodways - those parcels which are under the jurisdiction of Act 250 will need to comply with criterion 1D Flood Hazard Areas and River Corridors (FHARC) \*

*\*basically the reconnection of the stream to its historic floodplain and the river corridor*



# Individual Permit for Stream Alteration Activities

## Individual Permit (IP):

### Crossing Structures:

Not installing a stream crossing that complies with bankfull channel dimensions:

Clear span = Bankfull Width (Wbkf); Clear Rise = 4 x Bankfull Depth (Dbkf)

*Design Standards not feasible due to:*

1. Urban setting confined by unmovable public infrastructure or habitable structures
2. Stream setting with a sediment transport-dominated stream with a very high volume of coarse bedload (i.e., prone to high deposition and scour)

### Dam Removals:

1. Significant volume of accumulated sediment not being removed
2. Downstream water quality standards will be negative impacted

# **Designing and Permitting for Stream Crossings**

# Identification of Bankfull Stage on Perennial Streams

## *Identification of Bankfull Stage Vermont Stream Geomorphic Assessment*

*Vermont Agency of Natural Resources April 2004*

[https://dec.vermont.gov/sites/dec/files/wsm/rivers/docs/rv\\_identification\\_of\\_bankfull\\_stage.pdf](https://dec.vermont.gov/sites/dec/files/wsm/rivers/docs/rv_identification_of_bankfull_stage.pdf)

## **Field Indicators of Bankfull Stage**

*The following physical features that result from the erosion and deposition associated with the bankfull flow serve as indicators of the bankfull stage:*

- Nearly flat top of developing point bars: as the channel migrates across the valley it builds the active floodplain in its wake through the development of point bars
- Flat depositional benches or lateral bars
- Location of change on the bank from steep to a more gentle slope (break in slope)
- Erosion or scour features and often the lower extent of persistent woody vegetation.

\* Bankfull channel filled during bankfull flow, typically at 1.5-2 year recurrence interval

# Determining the Bankfull Channel Dimensions




**Figure 7** Example of a well developed floodplain in a system characterized by boulder size boundary material.

# DEC Hydraulic Geometry Equations for Bankfull Dimensions

Vermont Bankfull Channel Dimensions Table					
Drainage Area (mi <sup>2</sup> )	Bankfull Width (ft.)	Bankfull Depth (ft.)	Drainage Area (mi <sup>2</sup> )	Bankfull Width (ft.)	Bankfull Depth (ft.)
5	27	1.6	110	104	3.9
10	36	1.9	115	106	4.0
15	43	2.2	120	108	4.0
20	49	2.4	125	110	4.1
25	54	2.5	130	112	4.1
30	59	2.7	135	113	4.2
35	63	2.8	140	115	4.2
40	66	2.9	145	117	4.3
45	70	3.0	150	119	4.3
50	73	3.1	155	121	4.4
55	76	3.2	160	122	4.4
60	79	3.3	165	124	4.4
65	82	3.4	170	126	4.5
70	85	3.4	175	127	4.5
75	88	3.5	180	129	4.6
80	90	3.6	185	130	4.6
85	93	3.6	190	132	4.6
90	95	3.7	195	133	4.7
95	97	3.8	200	135	4.7
100	99	3.8	205	136	4.7
105	102	3.9	210	138	4.8

Drainage area can be measured using the U.S. Geological Survey Stream Stats Tool at <http://streamstats.usgs.gov/Vermont.html>







# **Stream Alteration Performance Standards**

# B.3.2 Performance Standards for SAGP Activities

**B.3.2.1. Equilibrium Standard** - An activity shall not change the physical integrity of the stream in a manner that causes it to depart from, further depart from, or impedes the attainment of the channel width, depth, meander pattern, and slope associated with the stream processes and the equilibrium conditions of a given reach of stream. The equilibrium standard is met when it can be shown that, following the stream alteration, the water flow, sediment, and woody debris produced by the watershed will be transported by the stream channel in such a manner that the stream maintains its dimension, general pattern, and slope with no unnatural aggrading (raising) or degrading (lowering) of the channel bed elevation along the longitudinal stream bed profile.

**In Reality... figure out where the project location is currently within the channel evolution process and then design the project for that stage**

**Stage influences bankfull dimensions**



## B.3.2 Performance Standards for SAGP Activities

**B.3.2.2. Connectivity Standard** - An activity shall not change physical stream forms or alter local channel hydraulics, natural streambank stability, or floodplain connectivity in a manner such that changes in the erosion or deposition of instream materials results in localized, abrupt changes to or disconnects within the horizontal alignment of streambanks or vertical profile of the stream bed. A person shall not, unless authorized by the Secretary, change the course, current, or cross-section of a watercourse so as to create a physical obstruction or velocity barrier to the movement of aquatic organisms or change the vertical stream bed profile in a manner that impedes the movement of aquatic organisms.

**Simplified... the project must maintain or restore bankfull dimensions, channel alignment and roughness, and bed slope while providing for AOP**

# **Stream Crossing Design Standards**

# Steps for Project Coverage under the SAGP

## **Field Visit with River Management Engineer (RME):**

Schedule site visit with RME to confirm bankfull dimensions, alignment, slope, other issues

## **Confirm Hydraulic Capacity:**

USGS Stream Stats and HY-8 model (FHWA) to confirm HW/D ratio and size E-stone

## **Design Plans:**

Sketch Plan or Engineering Plans – used communicate to contractor what will be installed

## **Application Submittal:**

Complete 2 page form, landowner signature, submit with fee, authorization < 30 days

## **Construction Inspections:**

Pre-construction Meeting then construction inspections

Final inspection by RME to confirm site compliance




# Stream Crossing Design Standards

## under the Stream Alteration General Permit (SAGP)

<b>SAGP Stream Crossing Minimum Design Requirements</b>	
<u>Open Width (span)</u>	Minimum 1 times $W_{bkf}$
<u>Open Height (rise)</u>	Minimum 4 times $D_{bkf}$
<u>Headwater to Depth (HW/D ratio)</u>	< 1.0 at Design Flow; minimum of Q25 *
<u>Structure Slope</u>	Match Long Bed Profile
<u>Embedded Depth</u>	Greater of E Stone Sizing or 30% of O.H
<u>Aquatic Organism Passage (AOP)</u>	Provided with ANR E-stone

\* **Design Flow** either the Q25 or Q50  
(based on the road classification)





Note: illustrations from Rivers and Roads Tier 2 field manual



# Stream Crossing Design Standards

## under the Stream Alteration General Permit (SAGP)

**Structure Size:** Based on field measurements



**Minimum Embedment Depth:** based on E-stone sizing



**HW/D Ratio at Design Flow: HY-8 model output**







# SAGP Permit Application Form



VERMONT DEPARTMENT OF ENVIRONMENTAL CONSERVATION  
**WATERSHED MANAGEMENT DIVISION**  
 RIVERS PROGRAM

**F. Please check the boxes for required attachments below. Applications submitted without the required attachments will not be forwarded for technical review.** (Additional information may be required after initial application review)

Location Map

**A PERMIT MAY BE REQUIRED FROM THE US ARMY CORPS OF ENGINEERS**

For information contact: US Army Corps of Engineers, VT Project Office, 8 Carmichael Street Suite 205, Essex Jct VT 05452 802-872-2893

APPROVALS OF SUBMITTED APPLICATIONS DO NOT CONVEY ANY LAND USE RIGHTS TO THE APPLICANT

ject indicate "Same" below):

2d. Zip:

For Stream Alteration Permitting Use Only. Appli

It is strongly recommended prior to your s  
 Environmental Conservation (DEC) - Rivers  
 please visit our website: <https://dec.vermont.gov>

**Site Visit Date:** \_\_\_\_\_

**Instructions:** To be administratively complete, p  
 attachments using ANR Online: [https://anronline](https://anronline.vermont.gov)  
 period, unless exempted by an emergency orde

**Permit Registration - \$200.00 Review**

**Permit Application - \$200.00 Review**

This is an urgent flood recovery projec

This project is receiving funding throu

The application fee for this permit is \$200.00

**Refund Policy:**

Please submit form, required attachments, and payment using  
 ANROnline at  
[https://anronline.vermont.gov/?formtag=WSMD\\_Intake](https://anronline.vermont.gov/?formtag=WSMD_Intake)

Permit Review Fees are non-refundable unless an  
 application is withdrawn prior to administrative review.

If unable to submit online, mail the completed application form and  
 required attachments along with a check for the application fee made  
 payable to State of Vermont to:

Vermont Department of Environmental Conservation  
 Watershed Management Division  
 1 National Life Drive, Davis 3  
 Montpelier, VT 05620-3522

Revised August 2023

**A. Applicant Contact Information (All i**

1. Name and Title: \_\_\_\_\_

Applicant Signature: \_\_\_\_\_ Date: \_\_\_\_\_

2a. Mailing Address: \_\_\_\_\_

Print Full Name, and title if applicable: \_\_\_\_\_

2b. Town: \_\_\_\_\_

Landowner Signature if applicable: \_\_\_\_\_ Date: \_\_\_\_\_

3. Phone: \_\_\_\_\_

Print Full Name, and title if applicable: \_\_\_\_\_

required):

on using the [ANR Atlas Map](#)

ing:

2d. Zip:

a, and proposed outcome)



# Standard Conditions of the SAGP Authorization

## AUTHORIZATION TO CONDUCT STREAM ALTERATION ACTIVITIES



**B.3.3. Stream Alteration Erosion and** authorized under this General Permit shall comply with the Vermont Water Quality

B.3.3.1. The permittee shall comply with construction stormwater pollution

B.3.3.2. All equipment shall be cleaned and gear oil leaks.

B.3.3.3. There shall be no discharge of sediment into the watercourse.

B.3.3.4. All areas of streambank disturbance shall be shaped and stabilized with vegetation. Streambank vegetation shall be minimized.

B.3.3.5. The method and duration of construction shall minimize disturbance of stream flow and sediment charge of sediment.

B.3.3.6. Work must be isolated from stream flow with appropriate sediment controls to the maximum extent practicable. Pumping from excavation areas shall be discharged to an overland area or off-stream settling basins such that the effluent shall be essentially clarified before reentering the stream flow.

B.3.3.7. If a permittee cannot comply with the foregoing requirements of Section B.3.3. of this General Permit, the permittee must propose alternative methods to avoid discharges of sediment and receive prior approval from the River Management Engineer before proceeding with work.

B.3.3.8. For those activities requiring reporting, governed by section C.2.2., C.2.3. and C.2.4 of this document, permittee must submit a water control plan detailing instream controls to the regional River Management Engineer, no less than 7 days prior to the start of construction and receive approval prior to the start of construction. Changes to an approved water control plan must be notified to the regional River Management Engineer for written approval.



# Submittal of Flow Control and Dewatering Plan

Prepared by the contractor – an illustration or description with sufficient detail to communicating control methods

Renaud Bros., Inc. 283 Fort Bridgman Road, Vernon, VT 05354 802-257-7383



R A Filskov & Sons, Inc.




Whipple Hollow Rd., Pittsford, VT Project – Culvert Replacement

October 8 – 11, 2024

## Water Flow Control Plan

Stream water will be controlled during the culvert replacement project by using a cofferdam immediately upstream of the culvert area. The water flow currently is minimal to non-existent.

The cofferdam will be constructed utilizing pre-cast concrete waste blocks with a poly liner to capture any water flow. The water captured will be pumped through a 3" line at a low velocity to minimize disturbance of stream bed down-stream of culvert installation area. Water will be filtered through a hay/grassy media prior to re-entry into the stream.





# Implementing Flow Control and Dewatering Plans

**Low point sump with stone for dewatering**



**Temporary bypass culvert for stream low flows**



Date & Time: Wed, Jul 17, 2024 at 11:31:28 EDT  
Bennington



**Cofferdam used to isolate the active work area**



# Site Inspections for Culvert/Bridge Replacement Projects

*Required under the VT DEC SAGP*

## **Pre-Construction Meeting**

Meeting at the site with the RME, contractor, engineer, and municipality or landowner to review design plans, project sequencing, construction schedule, E-stone bed infill material, extent of bed restoration, slope stabilization, and the dewatering and flow control plan

**\*\* Must notify the RME when construction begins and when the project is completed \*\***

*Recommended (the RME is not an inspector)*

## **During Construction by Engineer**

Elevation References - survey benchmarks for setting inverts and slope of new structure

Implementation of Flow Controls - confirm approved plan is implemented or modified

Structure Placement - slope, gradation of backfill material, and compaction requirements

E-stone - source and mixture gradation, placement and consistency, wetting to settle fines

Slope Stabilization – all disturbed soils stabilized by seed and mulch or VTrans stone fill

# E-Stone Gradation and Specifications

**E-stone is a custom mixture of native stream material and larger boulders or bank run with quarry stone**

## Streambed Stone Fill Design Guidance

Type	Q50 Velocity (fps)*	Embeddedness (in)	Substrate
E1	$V < 9$	18	0.0
E2	$9 < V < 11$	24	0.0
E3	$11 < V < 13$	36	0.0
E4	$13 < V < 15$	48	0.0

\*Maximum velocity should be based on a minimum 50-year flow rate (AEP 2% or Q50) and calculated at the structure

## Item xxx.xxx CY Streambed Stone Fill Specification

Type E1. The longest dimension of the stone shall be at least 18 inches, and at least 50 percent of the volume of the stone in place shall have a least dimension of 12 inches, and at least 25 percent of the particles shall have a maximum dimension of 2 inches and be well graded material.

Type E2. The longest dimension of the stone shall be at least 24 inches, and at least 50 percent of the volume of the stone in place shall have a least dimension of 18 inches, and at least 25 percent of the particles shall have a maximum dimension of 2 inches and be well graded material.

Type E3. The longest dimension of the stone shall be at least 36 inches, and at least 50 percent of the volume of the stone in place shall have a least dimension of 24 inches, and at least 25 percent of the particles shall have a maximum dimension of 2 inches and be well graded material.

at least 48 inches, and at least 50 percent of the volume of the stone in place shall have a least dimension of 36 inches, and at least 25 percent of the particles shall have a maximum dimension of 2 inches and be well graded material.

## Notes

- The streambed stone fill shall be hard, blasted, angular rock other than serpentine rock containing the fibrous variety chrysotile (asbestos). Similar sized river sediment is an acceptable alternative as is a mixture of angular material and river sediment.
- Stone placed inside of a closed structure shall be placed such that the structure is not damaged.
- Care shall be taken to limit segregation of the materials.
- Add sand borrow item as needed to seal the bed and prevent subsurface flow.
- There shall be no subsurface flow upon final inspection.

**\* Finer portion of E-stone helps seal the void spaces of the larger stone to keep stream flows on the surface**



# E-Stone Mixture, Placement, and Wetting Techniques

Salvaging the excavated stream bed material



Supplement mix with larger stone and/or fines



Closed top structures require smaller equipment

Split box culverts are ideal for top loading E-stone



# Reasons installed E-Stone does not function correctly

**Insufficient percentage of fines in the mixture**

**Consistency in mixture and in wetting the layer**



**Excessively large stone with no medium portion**

**Lack of natural sediment transport from upstream**

# **Permitting for Dam Removal and Stream Restoration**



# Submittals for Dam Removal and Stream Restoration

## Design Plans

Location Map: town, roads and parcels, dam impoundment, orthophoto image, etc...

Existing Conditions: features and topography within project limits which have importance

Proposed Conditions: proposed grades and features of dam removal/stream restoration.

Resource Boundaries: streams, wetlands, floodplains, river corridors, protected sites, etc...

Long Profile: usually 10-20 bankfull widths for crossings, need longer with dam removals due to influence of the impoundment on the stream channel extending beyond the dam


Cross-sections: views for each feature being constructed, note the XS locations on plans

Erosion Prevention and Sediment Controls: what practices are required and where used; details from VT DEC EPSC manual, maintenance requirements, and removal of practices

\* Construction Phasing/ Sequencing Plan: regulatory requirements vs contractor submittal

\* Dewatering and Flow Control Plan: management of stream flows and/or dewatering


# Submittals for Dam Removal and Stream Restoration






# Submittals for Dam Removal and Stream Restoration


METTAWEE RIVER LONGITUDINAL PROFILE (THROUGH PROPOSED MAIN CHANNEL)





METTAWEE RIVER LONGITUDINAL PROFILE (THROUGH PROPOSED MAIN CHANNEL)



METTAWEE RIVER LONGITUDINAL PROFILE (THROUGH PROPOSED MAIN CHANNEL)




# Submittals for Dam Removal and Stream Restoration




# Submittals for Dam Removal / Stream Restoration Projects

Scaling from drawings works in the office, include sufficient dimensions/details on plans!



TYPICAL CROSS SECTION

- TYPICAL CHANNEL DIMENSIONS ARE AS FOLLOWS:
  - LOW FLOW CHANNEL WIDTH = 6.75 FT
  - BANKFULL CHANNEL WIDTH = 20.3 FT
  - BANKFULL CHANNEL DEPTH = 1.1 FT
- SET LOW FLOW CHANNEL WIDTH TO APPROXIMATELY 1/3 OF THE BANKFULL CHANNEL WIDTH.
- ALIGNMENT OF THE LOW FLOW CHANNEL TO BE LOCATED IN THE FIELD DURING CONSTRUCTION BY THE PROJECT ENGINEER.
- DISTURBED BANKS TO BE REINFORCED WITH 2-3 FT BOULDERS AND TREES WITH ROOTWADS.
- PROPOSED CHANNEL TO BE CONSTRUCTED USING NATIVE CHANNEL BED MATERIAL FROM IMPOUNDMENT. MAINTAIN ROUGH AND IRREGULAR CROSS SECTION. ANY TREES REMOVED DURING CONSTRUCTION CAN BE USED WITHIN STREAM CHANNEL FOR HABITAT DIVERSITY. KEEP ROOTWAD INTACT IF POSSIBLE.




GRADE CONTROL  
BOULDERS SET  
BELOW STREAMBED

GRADE CONTROL DETAIL  
CROSS SECTION VIEW LOOKING UPSTREAM



# Submittals for Dam Removal / Stream Restoration Projects

## Phasing / Sequencing Plans – Prescriptive vs Descriptive, allow for contractor’s input





# Submittals for Dam Removal / Stream Restoration Projects

**Contractor Construction Schedule** – flexibility due to weather and instream work dates;  
 Normal - July 1 to October 1 or in streams with no rainbow trout - June 1 to October 1

Pelletier Dam 7/1/2022																											
ID	Task Name	Duration	Start	Finish	Jul 3, '22							Jul 10, '22							Jul 17, '22								
					T	F	S	S	M	T	W	T	F	S	S	M	T	W	T	F	S	S	M	T	W	T	
1	<b>Pelletier Dam</b>	<b>67 days</b>	<b>Fri 7/1/22</b>	<b>Mon 10/3/22</b>	[Gantt bar spanning from Fri 7/1/22 to Mon 10/3/22]																						
2	Mobilization	4 days	Tue 7/5/22	Fri 7/8/22	[Gantt bar from Tue 7/5/22 to Fri 7/8/22]																						
3	Sign Package	1 day	Thu 7/7/22	Thu 7/7/22	[Gantt bar on Thu 7/7/22]																						
4	Erosion Control	2 days	Thu 7/7/22	Fri 7/8/22	[Gantt bar from Thu 7/7/22 to Fri 7/8/22]																						
5	Dam Removal	5 days	Wed 7/6/22	Tue 7/12/22	[Gantt bar from Wed 7/6/22 to Tue 7/12/22]																						
6	Stream ByPass	5 days	Mon 7/11/22	Fri 7/15/22	[Gantt bar from Mon 7/11/22 to Fri 7/15/22]																						
7	Temp Access Road	5 days	Mon 7/11/22	Fri 7/15/22	[Gantt bar from Mon 7/11/22 to Fri 7/15/22]																						
8	Phase 1 - 4	27 days	Mon 7/18/22	Tue 8/23/22	[Gantt bar from Mon 7/18/22 to Tue 8/23/22]																						
9	Parking Lot Restoration	5 days	Mon 8/22/22	Fri 8/26/22	[Gantt bar from Mon 8/22/22 to Fri 8/26/22]																						
10	Demobilization	5 days	Mon 8/22/22	Fri 8/26/22	[Gantt bar from Mon 8/22/22 to Fri 8/26/22]																						

# Submittals for Dam Removal / Stream Restoration Projects

**Dewatering and Flow Control Plan** - Flexibility is critical to allow contractor to rapidly adapt to changing site conditions; adjustments for economical and environmental benefits

## Water Control Plan Notes

1. The suggested Water Control Plan in sequencing notes (to the right) is an example and for the purposes of project bidding.
2. The Contractor shall submit a Water Control Plan (Plan) for approval mobilization. The plan can follow Steps 7.1 through 7.6, or the Contractor alternate Plan. Overall, the Plan will be the Contractor's plan that meets requirements and is subject to approval by the Engineer. See specifications.
3. All permits relevant to the Plan are/will be located in the construction notes.
4. Work shall only be conducted during times of low flow. The contractor shall monitor weather, rainfall and storm warnings issued by the National Weather Service project and will remove all equipment and materials that may be affected by low flow conditions. All equipment is to be stored on high ground.

## General EPSC Plan Notes

1. The On-Site Coordinator shall inspect for runoff of visibly discolored sediment from the construction site as soon as reasonably possible during or after every snowmelt event which produces runoff from the construction site and develop mitigation options.







## 7. Implement Water Control Plan measures:

- 7.1. Begin work in Phase 1 and excavate impounded sediment at station 21+28 and use material to create an earthen berm cofferdam. Construct cofferdam to maintain flow in one portion of the channel, and perform work in opposite (dry) side of channel. Once work is complete on the dry side, redirect flow to that side and complete work in remaining portion of channel.
- 7.2. Grade channel and floodplain, and install channel bed features (i.e. steps & pools) per Sheet 8. Segregate and stockpile the excavated sediments, soils, stone material and any wood material and store in the stockpile areas as needed. Some of the stockpiled materials will be utilized in the restoration of the areas to be temporarily impacted (i.e. use excavated wetland soils for surfaces of floodplain benches).
- 7.3. Utilize dewatering sump when and where needed throughout excavations, to maintain work in the dry.
- 7.4. Continue removal of dam per extents and elevations on plans. Move material out of site via site access route. Temporarily place dam materials in storage pile areas as needed.
- 7.5. Haul out excess material via the site haul route.
- 7.6. Overall, perform work in phases (see phase boundaries this sheet) starting from upstream to downstream (start at Phase 1 and work sequentially to end at Phase 4) as Contractor backs out of site. As listed above, work will include channel and floodplain grading, construction of channel bed, removing timber mats and application of seed and mulch per Note 8 below in each of four phases.




# Submittals for Dam Removal / Stream Restoration Projects

## Erosion and Sediment Control Plan – standard details, flexibility for changing conditions


<p><b>STANDARD AND SPECIFIC DEWATERING SUMP</b></p>	<p>SYMBOL</p>  <p>NOT TO SCALE</p>		<p>SYMBOL</p> 
 <p>Discharge should be stabilized. The pit will be cloth wrapped and the discharge cloth be attached to the water source.</p>	<p>PLAN VIEW</p> 		
<p><b>Definition &amp; Scope</b></p> <p>A temporary pit which is constructed using pipe and stone for pumping excessive water from excavations to a suitable discharge area.</p> <p><b>Conditions Where Practice Applies</b></p> <p>Sump pits are constructed when water collects during the excavation phase of construction. This practice is particularly useful in urban areas during excavation for building foundations. It may also be necessary during construction activities that encounter high ground water tables in floodplain locations.</p> <p><b>Design Criteria</b></p> <p>The number of sump pits and their locations shall be determined by the contractor/engineer. A design is not required, but construction should conform to the general criteria outlined on Figure 3.3 on page 3.8.</p>	<p>PROFILE</p>  <p><b>CONSTRUCTION SPECIFICATIONS</b></p>		<p><b>CONSTRUCTION SPECIFICATIONS</b></p> <p>CONSTRUCTED BY PERFORMING A 12-24" DIAMETER STANDPIPE. EQUIVALENT AGGREGATE SHOULD BE PLACED IN THE CENTER. UPON INSTALLING THE STANDPIPE, THE PIT SURROUNDING SHOULD BE BACKFILLED WITH NYS DOT #2 OR EQUIVALENT AGGREGATE. THE STANDPIPE SHOULD BE PLACED 12-18" ABOVE THE LIP OF THE PIT. THE STANDPIPE SHOULD BE CONNECTED DIRECTLY TO A STORM DRAINAGE SYSTEM, WRAPPED WITH FILTERCLOTH BEFORE INSTALLATION. IT IS RECOMMENDED THAT 1/4"-1/2" HARDWARE CLOTH MAY BE PLACED AROUND THE STANDPIPE, PRIOR TO ATTACHING THE FILTERCLOTH.</p>
<p>A perforated vertical standpipe is placed in the center of the pit and surrounded with a stone screening material to collect filtered water. Water is then pumped from the center of the pipe to a suitable discharge area.</p>	<p><i>* Approved alternatives suggested by contractor</i></p>		<p>ADAPTED FROM DETAILS PROVIDED BY: USDA - NRCS, NEW YORK STATE DEPARTMENT OF TRANSPORTATION, NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION, NEW YORK STATE SOIL &amp; WATER CONSERVATION COMMITTEE</p> <p><b>DEWATERING SUMP PIT</b></p>

# Submittals for Dam Removal / Stream Restoration Projects

## Dewatering and Flow Control Plan – show details for intent of suggested control measures




\* Turbidity curtains do not function across flowing water



### Downstream Sediment Control Notes:

1. Downstream sediment control components include 1) a gravel berm placed the full width of the stream channel with its crest just above dry weather water surface elevation, positioned approximately 5-10' upstream of the silt curtain. The purpose of the gravel berm is to encourage a mild to moderate slow down of stream flow to promote settling of any suspended sediments upstream of the berm, and to also provide filtering (through the berm) of sediments that remain suspended. 2) A silt curtain as illustrated in the silt curtain detail found on this sheet.
2. The gravel berm will provide primary treatment of suspended sediment while the silt curtain will provide secondary treatment.
3. The channel bed material used for the gravel berm should be washed and void of any sands or fines prior to placement, per inspection and approval by the Engineer.
4. Check for collected sediment upstream of both components daily and remove sediment manually, placing removed material out of roadway.
5. In the event a runoff producing storm is predicted for the following day, remove any collected sediment from the channel at both components.
6. The Contractor is required to remove the gravel berm and silt curtain from the channel once all upstream earthwork is complete.



### NOTE:

1. SEDIMENTATION BASIN TO BE USED IF CONTRACTOR IS UNABLE TO FIND A SUITABLE DISCHARGE AREA FOR DEWATERING DISCHARGE PIPE.
2. ALL MATERIALS, LABOR, CONSTRUCTION, MAINTENANCE AND REMOVAL OF THE SEDIMENTATION BASIN, AND RESTORATION OF THE AREA SHALL BE INCLUDED IN ITEM 653, EROSION PREVENTION AND SEDIMENT CONTROL, DISPOSE OF FILTER BAGS WHEN FULL AND REPLACE.

# Site Inspections for Dam Removal / Stream Restoration

*Required under the VT DEC SAGP*

## **Pre-Construction Meeting**

Meeting at the site with the RME, contractor, engineer, and municipality or landowner to review design plans, project sequencing, construction schedule, extent of stream, wetland, and floodplain restoration, site stabilization, and implementation of the flow control plan

**\*\* Must notify the RME when construction begins and when the project is completed \*\***

*Recommended (the RME is not an inspector)*

## **During Construction by Engineer**

Pre-construction - survey benchmarks, flag protected resources, limits of construction

Implementation of Flow Controls - confirm approved plan is implemented and modified

Typical Restored Stream - excavation to armoring layer, channel/floodplain dimensions

Post-rainfall - check to see how site responded to flood event and modify as needed

Site Stabilization - all disturbed soils stabilized by seed and mulch and native plants

**\* Dam Structure - DSP requires design engineer to certify removal of the dam structure \***




# Resources for Dam Removals in Vermont

[https://dec.vermont.gov/sites/dec/files/wsm/rivers/docs/drw\\_usersguide.pdf](https://dec.vermont.gov/sites/dec/files/wsm/rivers/docs/drw_usersguide.pdf)

## User's Guide to Vermont Dam Removals

A Basic Handbook for Project Managers  
October 2009



[https://www.americanrivers.org/wp-content/uploads/2024/01/VTDamRemovalGuide\\_2023.pdf](https://www.americanrivers.org/wp-content/uploads/2024/01/VTDamRemovalGuide_2023.pdf)



# Useful Barrier Removal Websites

VT DEC Rivers Program River Management

<https://dec.vermont.gov/watershed/rivers/river-management>

Vermont Stream Crossing Handbook

<https://vtfishandwildlife.com/sites/fishandwildlife/files/documents/Learn%20More/Library/REPORTS%20AND%20DOCUMENTS/AOP/AOP%20HANDBOOK.pdf>

VT DEC Stream Alteration General Permit (SAGP) –

[https://dec.vermont.gov/sites/dec/files/wsm/rivers/docs/StreamAlterationGeneralPermit\\_2022-04-19.pdf](https://dec.vermont.gov/sites/dec/files/wsm/rivers/docs/StreamAlterationGeneralPermit_2022-04-19.pdf)

Technical Guidance for Identification of Perennial Streams-

[https://dec.vermont.gov/sites/dec/files/wsm/rivers/docs/rv\\_guidance\\_for\\_the\\_identification\\_of\\_perennial\\_streams.pdf](https://dec.vermont.gov/sites/dec/files/wsm/rivers/docs/rv_guidance_for_the_identification_of_perennial_streams.pdf)

Vermont Rivers & Roads Tier 2 and Tier 3 Trainings

<https://dec.vermont.gov/event/vermont-rivers-roads-tier-2-and-tier-3-training>